# SARDINIA RADIO TELESCOPE Project & Scientific Perspectives

# Isabella Prandoni Project Scientist SRT

INAF- Istituto di Radioastronomia Bologna





# **SRT PROJECT**



I. Prandoni, IRA – INAF, ITALY



#### **SRT MOST RELEVANT FEATURES:**

- Primary and Secondary Mirror Shaping:

**Basic antenna configuration**  $\rightarrow$  **<u>gregorian shaped</u>** 

obtained with mirrors "nearly" parabolic and elliptical.

"non classical" curves → better illumination of gregorian/BWG focus compared to standard configuration

Shaping generates **<u>null field in</u>** primary mirror <u>**central region**</u>, blocked by secondary mirror

Field redistributed throughout unblocked region, **increasing illumination efficiency** 

In addition, the *shaping* causes **<u>under-illumination</u>** of <u>the</u> <u>reflector</u> edge





TELESCOPE

#### SRT Shaping:

This choice **optimizes gregorian/BWG foci observations**, despite some loss in FoV → **no standing waves**, **no spillover** → **high efficiency spectroscopy** 

But it reduces the primary focus efficiency, as those observations uses the primary reflector only

For observations in primary focus classical parabolic profile has to be preferred

**→** Max eff. & FOV  $\leq$  20 GHz

**NB:** It is possibile to modify the primary reflector's geometry through **active surface techniques** 





#### **SRT Active Surface:**

#### **Gravitational deformations:**

A structural analysis (FEA – Finite Element Analysis) allows to define, for each elevation, variations in antenna's geometry due to its own weight.

A control system, made of one or two couple of inclinometers will allow **real time measures and corrections of antenna's geometry**.



#### Wind and thermal gradients:

On mirror surface pressure sensors installed. On alidade and quadrupod temperature sensors. Using data from all sensors possible to study antenna's behaviour under the effects of thermal gradients and wind pressure.

With a second FEA, it will be possible to link reflector deformations to climations to climations and recover surface accuracy.

## **SRT General Specifications**

	Up to 22GHz	Up to 100GHz		
Configuration	EL over AZ			
Elevation angular travel	from 5° to 90°			
Azimuth angular travel	± 270°			
Azimuth angular velocity	51deg/min			
	(if wind spee	d < 60  km/h		
Elevation angular velocity	30deg/min			
	(if wind spee	ed < 60 km/h)		
Global Surface accuracy (global rms from specifications of single structural elements)	630µm (sup. passiva)	185 μm ( <u>Phase 1</u> ) 119 μm ( <u>Phase 2</u> )		
Pointing accuracy (rms) – Normal Conditions	11 ÷ 2.7	7 arcsec		
Pointing accuracy (rms) – Precision Conditions	5 ÷ 1.8	arcsec		

80-100 GHz obs  $\rightarrow$  only in normal/precision conditions

#### **Observing Conditions**

Parameters	Precision	Normal
Wind (km/h)	< 15	< 40
Solar	Absent	Clear sky
Precipitations	Absent	Absent
Temperature	da – 10°C a 30°C	da – 10°C a 40°C
Temperature drift	< 3°C/h	< 10°C/h
Humidity	< 85%	< 90%

#### Active Surface:

Phase 1: End of antenna's assembly

(OPEN LOOP→ Finite Element Analysis).

\*

SRT

<u>Phase 2</u> : End of olographic campaign (measure of primary reflector panels' alignment).

Metrology technics are under evaluation (CLOSED LOOP).

#### **SRT MOST RELEVANT FEATURES:**

- Fast Wobbling of secondary mirror (wobbling time  $\leq$  1 sec for f  $\geq$  20 GHz)
- State-of-the-art Receivers/Backend (Wide Band/Multibeam)
- Site quality  $\rightarrow$  low RFI; wind speed (<v> = 4m/s); low content of water vapor
- SRT used also in Transmission
   → radar techniques: tracking
   experiments (ESA/ASI, NASA);
   Space science
- -Both SD and VLBI operations



R A D I O TELESCOPE

## **SRT SITE:**

Located in "Pranu Sanguni" close to a village named San Basilio, 35 km North of Cagliari.



Elevation	585 m
Longitude	$-09^{0}  14^{m}  40^{s}$
Latitude	+39 <sup>0</sup> 29 <sup>m</sup> 50 <sup>s</sup>





## **SRT SITE:**

#### Probability of measuring atmospheric opacity $\tau$ <0.1 along the year





## RECEIVER SET: 0.3 – 100 GHz

Banda (Sigla)	v <sub>o</sub> (GHz)	λ (cm)	N° Ricevitore	v <sub>Lsky</sub> (GHz)	v <sub>Hsky</sub> (GHz)	∆ v/ <sub>vc</sub> (%)	Banda ricevitore (MHz)	Temperatura di rumore (K)	Configurazione
Р	<u>0.3</u>	90	1P	0.31	0.42	12	2×110	30	Coassiale a 1.5 GHz
L	0.6	50	<u>ar</u>	0.58	0.62	- t	2X40	25	
Ľ	1	30	1P	0.70	1.30	60	2X600		
L	<u>1.5</u>	18-21	2P	1.30	1.80	32	2×500	5	Coassiale a 0.3 GHz
S	2	13	2P	2.20	2.36	7	2X160	J	Coassiale a 8 GHz
S	3	10	ЗP	2.36	3.22	27	2×860		
S	4	7.5	ЗP	3.22	4.30	32	2X1080		
С	5	6	1B	4.30	5.80	32	2X1500	15	Monofeed
С	Z	5	2B	5.70	7.70	30	2×2000	15	Monofeed
X	8	3.6	2P	8.18	8.98	9	2X800		Coassiale a 2 GHz
Х	9	3.3	1G	7.50	10.40	32	2X2000	10	
Ku	13	2.3	2G	10.30	14.40	33	2×2000	14	
Кц	17	1.8	3G	14.40	19.80	32	2X2000	18	
К	23	1.3	4G	19.00*	26.50	33	2×2000	21	Multifeed (7 elementi)
Ka	32	0.9	5G	26.00	36.00	32	2X2000	25	
Q	43	0.7	6G	35.00	50.00	31	2X2000	40	
E	86	0.4	7G	70.00	90.00	25	2X2000	90	
W	100	0.3	8G	90.00	115.00	25	2X2000	100	

# **FIRST LIGHT INSTRUMENTATION**



#### 18-26 GHz

**Multi-feed** 

# K-band Surveys

- Pulsar Research.
  - Search for Recycled/msec pulsars in Galactic
    - **Center**  $\rightarrow$  new binary systems

msec pulsar/BH  $\rightarrow$  gravitational tests

#### - Continuum Surveys:

- Free-free emission mapping of the Galactic Plane

→ Ultra-Compact HII Regions

- Deep Fields [SRT confusion limit: 50-70 µJy (rms)]

→adding information @  $\ge$  10 GHz → high-z/low lum. AGNs

#### - Line Surveys:

- Search of H<sub>2</sub>O masers in Local Group

→ Distance & 3D kinematics → Dark Matter & Cosmology

- Unbiased Mapping NH<sub>3</sub> in Galactic Plane

→ Astrochemistry of Star formation Regions







# 18-26 GHz

**Multi-feed** 

# **ASTROCHEMISTRY with SRT**

Unbiased Mapping of Ammoniaca in star formation regions

NH<sub>3</sub>(1,1) & (2,2) at ~23.7 GHz
+ hyperfine transitions [τ]
→ T of molecular clouds

In sinergy with JCMT, Herschel/Spitzer, APEX, ALMA

 → Find pre-stellar cores
 → Study of physical and chemical properties of various components: gas, dust, stars



Courtesy P. Caselli & J. Brand

20/90 cm

**Dual Band** 

# **PULSARS with SRT**

LEAP: Large European Array for Pulsars

(UE grants for 5 years)

Combining coherently the 5 major European telescopes
 best telescope in L-band for timing before SKA

 • dual band 20+90 cm receiver mounted on SRT → unique capability in removing interstellar medium effects

<u>Ultra precise Timing of Pulsar</u>: Detection of space-time perturbations in residual timing analysis

Leader Experiment for detection of Gravitational Waves from Cosmological Background and/or from SMBH in local merging galaxies





Courtesy A. Possenti





# **PROGRESS STATUS**

### **ANTENNA FOUNDATIONS**

Completed beginning 2006





### **AZIMUTH TRACK**



## **ALIDADE AND ACTUATORS**



#### Actuators



Designed by IRA

Tested and stored in Medicina



TELESCOPE

## **REFLECTOR BACKUP STRUCTURE**

Bus assembling on ground  $\rightarrow$  December 2008



## **INSTRUMENTATION: 1st LIGHT RECEIVERS**



22 GHz multibeam receiver Mounted on 32 m in Medicina



6.7 GHz mono feed receiver

Dual frequency (300 MHz / 1400 MHz) coaxial receiver

# higher frequency receivers are on the agenda !





## **INSTRUMENTATION: BACK-ENDS**



Analogic Total power Backend 7x2 outputs

Pulsar Digital Filter Bank

Multipurpose digital spectrometer



#### Estrela Workshop, January 2009

#### I. Prandoni, IRA – INAF, ITALY

	SRT_ SCHEDULE PLAN FABRICATION, TRANsPORT , Erection, Panel Installation & Plants							
					2008 2009			
	Tite	Duration	Start	Finish	2005 01 102 103 104 105 105 107 108 109 110 111 12 01 102 103 104 105 106 107 108 109 110 111 12 01 102 103 104 105 106 107 108 109 110 111 12 01 102 103 104 105 106 107 108 109 110 111 12	2010 01 02 03 04 05 06 07 08		
	ERECTION	1019 dys	Mon 06/02/06	Thu 31/12/09				
	Track preweiding and preparation	72 dys	Mon 06/02/06	Tue 16/05/06	Track prevelding and preparation			
	Site transfer	56 dys	Wed 17/05/06	Wed 02/08/05	Sthe transfer			
	Track, accembly and welding	185 dys	Thu 03/08/06	Wed 18/04/07	Trock, ascembly and welding			
-	Greace remove and concrete rectoration	75 dys	Thu 19/04/07	Wed 01/08/07	Greace remove and concrete rectoration			
H	Track, grouting, nardening, preccrecc	56 GyS	Thu 02/06/07	Thu 18/10/07	rzok grouine, nardenne, precise			
H	Track Machining, Final measurement	4/ 035	Man D//D//US	Tue Us/Us/Us	a roo maouning, rinai mescuremente			
H	Pinfie Rearing and Ar. Cable wrap, bardening	120 due	Map 16/04/07	Ed 12/10/07		<del></del>		
H	Alidade	225 dys	Thu 22/11/07	Wed 01/10/08				
E	Erection	105 dys	Thu 22/11/07	Wed 16/04/08				
E	Welding	150 dys	Thu 20/12/07	Wed 16/07/08				
Г	Alignment upper part, weiding	43 dys	Thu 17/07/08	Mon 15/09/08	lannent uder part, wolding			
Е	Measurement, weighting	12 dys	Tue 16/09/08	Wed 01/10/08	Meadurement, weighting			
	Alidade acceptance	0 dys	Wed 01/10/08	Wed 01/10/08				
Ľ	EI. Wheel, pillow block, drive	195 dys	Mon 20/10/08	Fri 17/07/09				
ĽŰ,	Partial Preassembly on ground, partial welding	40 dys	Mon 20/10/08	Fri 12/12/08	I III III Preaseembly on ground, partial Preaseembly on ground, partial weiding			
-	Erection on Alidade	55 dys	Mon 10/11/08	FR 23/01/09				
-	weiging hallast constate	70 dys	Mon 26/01/09	FR 01/05/09				
-	El Wheel Acceptance	D dys	Eri 08/05/09	Fri 08/05/79				
-	remaining works	50 dys	Mon 11/05/09	Fri 17/07/09				
	BUS	360 dys	Mon 12/05/08	Fri 26/08/08				
1	Assembling on ground, adjusting	150 dys	Mon 12/05/08	Fri 05/12/08				
	welding on ground	80 dys	Mon 08/12/08	Frl 27/03/09	weiding on ground			
	Geometrical Acceptance on ground	0 dys	Fri 27/03/09	Frl 27/03/09				
	Lifting, connecting, weiding	50 dys	Mon 11/05/09	Frl 17/07/09				
	BUS acceptance inner	0 dys	Fit 12/06/09	Frl 12/06/09				
	BUS Final acceptance	0 dys	Wed 26/08/09	Wed 25/08/09	2008			
-	remaining works	50 0ys	Moh 20/07/09	Fil 25/09/09	Personal and the second s	**		
-	Energies from an annuad	15 due	Tue 16/12/08	Med 2arbeide				
-	Election Ages incl. SR PEP on BUS	12 dvs	Mon 15/06/09	Tue 30/06/09	Spaller April 19 19 19 19 19 19 19 19 19 19 19 19 19	on BUS		
	Erection Quadripod legs	8 dys	Mon 20/07/09	Wed 29/07/09				
	Quadripod Acceptance	0 dys	Wed 29/07/09	Wed 29/07/09				
	remaining works	40 dys	Thu 30/07/09	Wed 23/09/09		ks i i i i i i i i i i i i i i i i i i i		
	Rest of works	260 dys	Mon 22/12/08	Fri 18/12/09				
	beamguide	165 dys	Mon 22/12/08	Fr! 07/08/09				
_	Beam guide acceptance	0 dys	Fri 07/08/09	Fri 07/08/09				
_	painting	100 dys	Thu 18/06/09	Wed 04/11/09				
-	cerve locialistico. Ellina	20 dys	Mon 3 (JDB/DB	Ext delitorde		Intion Elife		
-	servo final commissioning	50 dys	Mon 12(10/09	Fel 18/12/09		anon, Energy and an		
	Servo main movement tests	5 dys	Thu 05/11/09	Wed 11/11/09		nain movement tests		
-	Servo appeptance	D dys	Wed 11/11/09	Wed 11/11/09				
		g	in a sure of the second	Survey and servey as a server				
	Subreflector	161 dys	Mon 01/08/08	Mon 13/04/09				
	Design, Fabrication, erection site installation frame	80 dys	Mon 01/09/08	Frl 19/12/08	Essen, Fabrication, erection atte installation frame			
	Erection Subreflector on ground	30 dys	Tue 16/12/08	Mon 26/01/09				
-	Installation Apex, SR Post, SR Into sile manie	20 dys	Tue 2//01/09	Mon 23/02/09	International door and a second door a sec			
-	Panel allogment 45*	20 dys 15 dys	Tue 24/02/05	Mon 13/04/09				
	ranci organicati 45	12 492	100 2403103	100110104002				
	Main Reflector	234 dys	Mon 09/02/09	Thu 31/12/09				
	Installation of actuator pads, prealignment	25 dys	Mon 09/02/09	Frl 13/03/09	inctaliation of social grading and the social s			
	Alignment of actuator pads	35 dys	Thu 09/07/09	Wed 26/08/09				
	Installation of actualors, cabling	25 dys	Thu 13/08/09	Wed 16/09/09				
	Panel installation	28 dys	Thu 17/09/09	Mon 26/10/09				
	Panel alignment for 45*	20 dys	Tue 27/10/09	Mon 23/11/09				
_	Alghment main-sub-reflector, look up table	28 0ys	TUE 24/11/09	100 31/12/09				
-	Plage	950 dur	Mon 17/11/29	Erl 30/10/29		┍┼┼┼┼┼┼┼		
-	cable travs	180 dys	Mon 17/11/08	Fri 24/07/09				
-	power distribution	65 dvs	Mon 29/06/09	Fri 25/09/09				
-	cooling system installation	25 dys	Mon 28/09/09	Frl 30/10/09		ystem installation		
	Inst., cabling minor syst. Control	20 dys	Mon 14/09/09	Fri 09/10/09		a minor eyet. Control		
	balast cover, design fabrication, erection	60 dys	Mon 09/03/09	Fri 29/05/09	Antenna assempling -> Eng 2009 Trainet over antegration	, ereation		
		8 - 18	Constantine of	laan araasad				
	Taking over	0 dys	Thu 31/12/09	Thu 31/12/09	. 4 184 1 4 18 18 18 18 18 19 14 14 14 14 14 14 14 14 14 14 14 14 14	31/12		

# **SRT in 2010**





## Be ready to submit your proposal!



http://srtproject.ca.astro.it

